









1 : 100

FOR	COMMENT	PLANNING	CONSTRUCTION	AS-BUILT
Drawing No	Project Number			Sheet No A101

				
W1	W2	W3	D1	

Window Legend



1 : 50

Window Schedule				
Type Mark	Width	Height	Type	Count
W1	1100	1500	Glazed Louvred Window-	24
w2	600	800	Glazed Louvred Window	3
W3	1500	1200	Aluminium Glazed Sliding Window	2

Door Schedule				
Type Mark	Width	Height	Type	Count
D1	1500	2100	1510 x 2110mm	5
D2	750	2110	810 x 2110mm	3

NOTES

ALL DRAWINGS ARE IN MILLIMETERS
DO NOT SCALE FROM DRAWINGS

- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH RELEVANT ARCHITECTURAL DRAWINGS
- CONCRETE SHOULD HAVE A COMPRESSIVE STRENGTH OF 30N/MM2 AFTER 28 DAYS.
- MACHINE CRUSHED AGGREGATES TO BE USED SHOULD BE 20mm SIZE GRADED DOWN TO 10mm
- FINE AGGREGATES SHOULD BE FREE OF ORGARNIC
- COVER TO REINFORCEMENT SHOULD BE:-
 - BASE = 50mm
 - COLUMNS = 30mm
 - BEAMS = 25mm
 - SLABS = 25mm
- FRESHLY CAST CONCRETE SHOULD BE WELL VIBRATED AND KEPT CONTINUOUSLY WET FOR AT LEAST 7 DAYS
- ALL EXTERNAL SUBSTRUCTURE BLOCK WALL SHOULD BE 225mm thick.



MULTI - BUILD LIMITED

Planners, Engineers and Project Management.
email: freearchconsult@gmail.com
TEL: +233(0)501393 772

Client

**MINISTRY OF EMPLOYMENT
AND LABOUR**

Project

**RENOVATION OF SLECTED
LABOUR OFFICES- TARKWA**

Drawing Title

DOOR WINDOW SCHEDULE

Scale : 1 : 50

Drawn : Author

Date : Issue Date

Check by :Checker

A3

FOR

COMMENT

PLANNING

CONSTRUCTION

AS-BUILT

Drawing
No

Project Number

Sheet
No

A102